19.0.1C Location: Date: 02-26-2021

Contract:

SN:

Engineer: Revision: Base Study Case: LF

IEEE_10_BUS Filename: Config.: Normal

Electrical Transient Analyzer Program

Load Flow Analysis

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total
Number of Buses:	1	0	9	10
				Line/Cable/

XFMR3

Reactor 0 0 0 Number of Branches:

Busway

Impedance

Tie PD

Total

Method of Solution: Adaptive Newton-Raphson Method

XFMR2

Maximum No. of Iteration:

0.0001000 Precision of Solution:

System Frequency: 60.00 Hz

Unit System: English

IEEE_10_BUS Project Filename:

Output Filename:

Project: ETAP Page: 2 19.0.1C Location: Date: 02-26-2021 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: IEEE_10_BUS Config.: Normal

Adjustments

	Apply	Individual	
Tolerance	Adjustments	/Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 02-26-2021

Contract:

Engineer:

Filename:

IEEE_10_BUS

SN:

Study Case: LF Revision: Base

Config.: Normal

Bus Input Data

								Lo	ad			
Bus			Initial Vo	oltage	Consta	Constant kVA		tant Z	Const	ant I	Gen	eric
ID	kV	Sub-sys	% Mag.	Ang.	kW	kvar	kW	kvar	kW	kvar	kW	kvar
Busl	23.000	1	100.0	0.0								
Bus2	23.000	1	100.0	0.0	1840.0	460.0						
Bus3	23.000	1	100.0	0.0	980.0	340.0						
Bus4	23.000	1	100.0	0.0	1790.0	446.0						
Bus5	23.000	1	100.0	0.0	1598.0	1840.0						
Bus6	23.000	1	100.0	0.0	1610.0	600.0						
Bus7	23.000	1	100.0	0.0	780.0	110.0						
Bus8	23.000	1	100.0	0.0	1150.0	60.0						
Bus9	23.000	1	100.0	0.0	980.0	130.0						
Bus10	23.000	1	100.0	0.0	1640.0	200.0						
Total Number of Buses: 10					12368.000	4186.001	0.000	0.000	0.000	0.000	0.000	0.000

G	eneration Bus	1		Voltage			Generation	kvar Limits		
ID	kV	Type	Sub-sys	% Mag.	Angle	kW	kvar	% PF	Max	Min
Busl	23.000	Swing	1	100.0	0.0					
						0.000	0.000			

Contract:

Location: 19.0.1C Date: 02-26-2021

SN:

Engineer: Study Case: LF Revision: Base

Filename: IEEE_10_BUS Config.: Normal

Impedance Input Data

Impedance	Positive	Sequence Im	pedance		
ID	R	X	Y	Unit	
Z1	0.1233	0.4127	0	Ohm	
Z2	0.014	0.6057	0	Ohm	
Z3	0.7463	1.205	0	Ohm	
Z4	0.6984	0.6084	0	Ohm	
Z5	1.9831	1.7276	0	Ohm	
Z6	0.9053	0.7886	0	Ohm	
Z7	2.0552	1.164	0	Ohm	
Z8	4.7943	2.716	0	Ohm	
Z9	5.3434	3.0264	0	Ohm	

Location: 19.0.1C Date: 02-26-2021

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: IEEE_10_BUS Config.: Normal

Branch Connections

CKT	/Branch	Co	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base					
ID	Туре	From Bus	To Bus	R	X	Z	Y			
Z1	Impedance	Bus1	Bus2	2.33	7.80	8.14				
Z2	Impedance	Bus2	Bus3	0.26	11.45	11.45				
Z3	Impedance	Bus3	Bus4	14.11	22.78	26.79				
Z4	Impedance	Bus4	Bus5	13.20	11.50	17.51				
Z5	Impedance	Bus5	Bus6	37.49	32.66	49.72				
Z6	Impedance	Bus6	Bus7	17.11	14.91	22.70				
Z 7	Impedance	Bus7	Bus8	38.85	22.00	44.65				
Z8	Impedance	Bus8	Bus9	90.63	51.34	104.16				
Z9	Impedance	Bus9	Bus10	101.01	57.21	116.09				

Location: 19.0.1C Date: 02-26-2021

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: IEEE_10_BUS Config.: Normal

LOAD FLOW REPORT

Bus	s	Volt	age	Gener	ation	Lo	ad		Load Flow	7			XFMR
ID	kV	% Mag.	Ang.	kW	kvar	kW	kvar	ID	kW	kvar	Amp	%PF	%Тар
* Bus1	23.000	100.000	0.0	13151.8	5222.7	0.0	0.0	Bus2	13151.760	5222.650	355.2	92.9	
Bus2	23.000	99.290	-0.5	0.0	0.0	1840.0	460.0	Bus1	-13105.090	-5066.429	355.2	93.3	
								Bus3	11265.090	4606.429	307.7	92.6	
Bus3	23.000	98.737	-1.3	0.0	0.0	980.0	340.0	Bus2	-11261.110	-4434.398	307.7	93.0	
								Bus4	10281.110	4094.398	281.3	92.9	
Bus4	23.000	96.340	-2.3	0.0	0.0	1790.0	446.0	Bus3	-10103.890	-3808.256	281.3	93.6	
								Bus5	8313.892	3362.256	233.7	92.7	
Bus5	23.000	94.801	-2.7	0.0	0.0	1598.0	1840.0	Bus4	-8199.492	-3262.598	233.7	92.9	
								Bus6	6601.491	1422.599	178.8	97.8	
Bus6	23.000	91.717	-3.7	0.0	0.0	1610.0	600.0	Bus5	-6411.270	-1256.885	178.8	98.1	
								Bus7	4801.269	656.887	132.6	99.1	
Bus7	23.000	90.716	-4.1	0.0	0.0	780.0	110.0	Bus6	-4753.493	-615.270	132.6	99.2	
								Bus8	3973.495	505.269	110.8	99.2	
Bus8	23.000	88.895	-4.6	0.0	0.0	1150.0	60.0	Bus7	-3897.752	-462.371	110.8	99.3	
								Bus9	2747.752	402.372	78.4	98.9	
Bus9	23.000	85.869	-5.4	0.0	0.0	980.0	130.0	Bus8	-2659.305	-352.266	78.4	99.1	
								Bus10	1679.309	222.263	49.5	99.1	
Bus10	23.000	83.750	-6.0	0.0	0.0	1640.0	200.0	Bus9	-1640.001	-200.000	49.5	99.3	

^{*} Indicates a voltage regulated bus (voltage controlled or swing type machine connected to it)

[#] Indicates a bus with a load mismatch of more than 0.1 MVA

ETAP Page: 7 Project:

19.0.1C Location: Date: 02-26-2021

Contract:

Engineer: Revision: Base Study Case: LF

IEEE_10_BUS Filename: Config.: Normal

Bus Loading Summary Report

Directly Connected Load

Total Bus Load

SN:

Bus	Bus		Constant kVA		Cons	Constant Z		stant I	Ger	neric				Percent
ID	kV	Rated Amp	kW	kvar	kW	kvar	kW	kvar	kW	kvar	kVA	% PF	Amp	Loading
Bus1	23.000										14150.790	92.9	355.2	
Bus2	23.000		1840.000	460.000							14050.340	93.3	355.2	
Bus3	23.000		980.000	340.000							12102.750	93.0	307.7	
Bus4	23.000		1790.000	446.000							10797.750	93.6	281.3	
Bus5	23.000		1598.001	1839.999							8824.751	92.9	233.7	
Bus6	23.000		1610.001	599.998							6533.309	98.1	178.8	
Bus7	23.000		779.999	110.000							4793.147	99.2	132.6	
Bus8	23.000		1150.000	60.000							3925.081	99.3	110.8	
Bus9	23.000		979.996	130.003							2682.535	99.1	78.4	
Bus10	23.000		1640.001	200.000							1652.151	99.3	49.5	

^{*} Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating). # Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:		ETAP	Page:	8
Location:		19.0.1C	Date:	02-26-2021
Contract:			SN:	
Engineer:		Study Case: LF	Revision:	Base
Filename:	IEEE_10_BUS	Stady Castr 21	Config.:	Normal

Branch Losses Summary Report

	From-To	Bus Flow	To-From	Bus Flow	Los	sses	% Bus V	/oltage	Vd % Drop
Branch ID	kw	kvar	kw	kvar	kW	kvar	From	То	in Vmag
Z1	13151.8	5222.7	-13105.1	-5066.4	46.7	156.2	100.0	99.3	0.71
Z2	11265.1	4606.4	-11261.1	-4434.4	4.0	172.0	99.3	98.7	0.55
Z3	10281.1	4094.4	-10103.9	-3808.3	177.2	286.1	98.7	96.3	2.40
Z4	8313.9	3362.3	-8199.5	-3262.6	114.4	99.7	96.3	94.8	1.54
Z5	6601.5	1422.6	-6411.3	-1256.9	190.2	165.7	94.8	91.7	3.08
Z6	4801.3	656.9	-4753.5	-615.3	47.8	41.6	91.7	90.7	1.00
Z7	3973.5	505.3	-3897.8	-462.4	75.7	42.9	90.7	88.9	1.82
Z8	2747.8	402.4	-2659.3	-352.3	88.4	50.1	88.9	85.9	3.03
Z9	1679.3	222.3	-1640.0	-200.0	39.3	22.3	85.9	83.8	2.12
					783.8	1036.7			

^{*} This Transmission Line includes Series Capacitor.

Location: 19.0.1C Date: 02-26-2021

Contract:

Engineer: Study Case: LF Revision: Base

Filename: IEEE_10_BUS Config.: Normal

Alert Summary Report

% Alert Settings

SN:

	Critical	Marginal
Loading		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
Generator Excitation		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

Critical Report

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus10	Bus	Under Voltage	23.000	kV	19.263	83.8	3-Phase
Bus5	Bus	Under Voltage	23.000	kV	21.804	94.8	3-Phase
Bus6	Bus	Under Voltage	23.000	kV	21.095	91.7	3-Phase
Bus7	Bus	Under Voltage	23.000	kV	20.865	90.7	3-Phase
Bus8	Bus	Under Voltage	23.000	kV	20.446	88.9	3-Phase
Bus9	Bus	Under Voltage	23.000	kV	19.750	85.9	3-Phase

Marginal Report

Dev	ice ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus4	В	us U	Jnder Voltage	23.000	kV	22.158	96.3	3-Phase

Project: ETAP Page: 10 19.0.1C Location: Date: 02-26-2021 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: IEEE_10_BUS Config.: Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	kW	kvar	kVA	% PF	
Source (Swing Buses):	13151.8	5222.7	14150.8	92.94 Lagging	
Source (Non-Swing Buses):	0.0	0.0	0.0		
Total Demand:	13151.8	5222.7	14150.8	92.94 Lagging	
Total Motor Load:	12368.0	4186.0	13057.2	94.72 Lagging	
Total Static Load:	0.0	0.0	0.0		
Total Constant I Load:	0.0	0.0	0.0		
Total Generic Load:	0.0	0.0	0.0		
Apparent Losses:	783.8	1036.7			
System Mismatch:	0.0	0.0			

Number of Iterations: 3